

June 20 1936

call for survey and plat
of lot 6 Block 18 Lake Shore
Manor

for B. R. Klekamp
No. 140 S. Dearborn St.
Chicago, Ill.

Iron stks to be set at 4 Cors
2 blue prints called.

Wanted Monday June 22-1936

Dimensions of lot as per
Original plat Lake Shore Drive
Bldg 50' Lake Shore line 55'
Line 5+6 132' Line 6+7 131'

Iron stks should be found
on 5-6 line, as this was
re-surveyed in

67.94, 2.35, 70.29

4.80

4.76

4.77

7.56

10.5' to curb line

later at 2 1/2' inside curb


Normal level of Lake 57'

Length of later at 7.7' (alt)

Wye to curb 10.5'

LM-38

A
B



Lower step to Fyrrrell Hook

Point at wye,

Curb elevation

elc. of walk

elc. of ground 15' in lot,

Made 7 B. ps

7-217-SK

20 1936

Survey and plat
Block 18 Lake Shore

R. Klekamp
S. S. Barn ST.

To be set at 4 Cors
ints called.

Monday June 22-1936

one of lot as per

1. plat Lake Shore Plg
Lake Shore Plg

132 Line 647/1311

45 should be found

ne as this was

ved in

57029 B.M. N.E. Cor

65.44 5980.5.69

65.53 59255.58

As there has been some difficulty in locating and laying sewers to some of the properties in this subdivision due to several unavoidable conditions we give you more complete data which we hope will overcome these difficulties.

Two manholes are used in determining these data one to the North 126 1/2 of Lot 6 block 18 and one to the south of this location App. 40 ft. Sower is in a straight line between manholes.

The grade of the main sewer is 2.2%
The lateral is laid at 126 1/2 ft. south of North Manhole.

There is a notch in pavement over the connection.

The lateral is laid 7.7 feet east, 6" pipe and ends 2 1/2' inside the curb. It is close to center of lot. A notch is made in top of curb and pavement.

The elevation of the pavement over the connection is 66.49

The elevation of the invert at connection is 66.60

The elevation of curb at end of lateral is 67.03

The elevation of lateral at end 69.25

The end of lateral is 2 1/2' inside of curb.

The lot at a point app. 16 ft east of curb 59.79

The normal level of the lake is 67.

The grade of the laterals is 2 1/2%

The bench mark used is the N.E. Cor. of the lower step of the south house of the two houses to the west.

The bench mark elevation is of the bench mark is 67.94' by the city's datum plane.

Point at curb
Curb elevation

7-217-SK