

39

May 5 1916

F.D. Countess, Ryerston
Per F.J. TyrrellDetermined courses of lines ~~AB~~ XY, MN & distance MOFor line AB set transit 4' S. of ^{post} (1) and 16' E. of post (3)~~Post (1)~~ and sighted on stake

in line with post (2) and

turned alidade to sight on

point 16' E. of post (4) angle

 $88^{\circ} 44'$ line AX S. $14^{\circ} W$.line AB is S. $88^{\circ} 33' E$.

Set transit 16' E. of (4) &

sighted on (6) and turned to

(1) angle $90^{\circ} 30'$ line XY S. $89^{\circ} 44' W$.

Set transit 4' E. of M. and

sighted on (6) and turned


to N. angle $92^{\circ} 26'$ line PL S. $16' E$.line MN N. $87^{\circ} 50' W$

line MO 37.6'

Alberta

XY, MN & distance MO

and 16' E. of post (3)



L-3-6 ✓

L-3-6 B ✓

L-3-6 C ✓

117-252-lk