

Construction Site Erosion Control Permit Application

Small Project Sites
Land Disturbing Activities Less than 1 acre

Walworth County Land Conservation Division
100 W. Walworth - Room 222
Elkhorn, WI 53121

Authority: Chapter 26-Article II, Walworth Co. Code of Ordinances
Walworth County Website: www.co.walworth.wi.us
Phone: 262.741-4972 Fax: 262.741-4973

Applicant Name: WANDA KOCHANIAK
Print Name

Contractor Name: GREGORY WHITE
Print Name

Address: N. 6513 ANDERSON DR.
DELAVER WI 53115
City State Zip

Address: W7515 SHOREWOOD TER
DELAVER WI 53115
City State Zip

Phone: 262-728-1741 Cell: _____

Phone: _____ Cell: 262-729-1181

Fax: SAME email: _____

Fax: _____ email: _____

Project Description: Attach the Project Site Plan and Soil Erosion and Sediment Control Plan

Total Land Disturbance Planned (square feet):	Square Feet
Total Area Disturbed Greater than 10,000 square feet (circle one)	Yes <u>No</u>

Check project description		
☒ Deck (post-hole construction)	☐ Pool Construction (Above Ground)	☒ Stairway (post-hole construction)
☐ Deck (excavated)	☐ Pool Construction (In-Ground)	☐ Stairway/walkway (excavated)
☐ Boathouse	☐ Spoil Spreading	☐ Driveway Construction
☐ Utility (Describe) _____ lin. ft	☐ Demolition:	☐ Parking Area/lot
Type: _____	☐ Landscaping	☐ Pond Construction/Spoil Spreading
Structures: Yes No	☐ Retaining walls	Planned Pond Depth: _____ feet
	☐ Other: _____	☐ Pond Maintenance

Project Location:

Shoreland (circle) Yes No Waterfront (circle) Yes No

Tax Key Parcel #: CCR00069

Municipality: WALWORTH COUNTY Section: _____

Subdivision: CRYSTLE BOWL

Project Site Address: N. 6513 ANDERSON DR.

I certify that I am the owner or the authorized representative of the owner of the property that is subject to this Permit Application. I certify that the information contained on this form and on the attachments are true, accurate and complete. I agree to comply with all applicable codes, statutes and ordinances and the conditions of this plan approval. I understand that the approval of the plan and permit creates no legal liability, expressed or implied of the Walworth County Land Use and Resource Management Department.

The applicant/landowner understands by submitting this application, Walworth County staff may enter upon the parcel, as described above, for the purpose of obtaining information necessary to review the permit application, prepare the permit approval and inspect construction activities.

Applicant Signature: _____

Date: 11/16/2010

Office Use Only:

Plan and Permit Application Reviewed by: DPD (name)

Base Fee: _____


Compliance Inspection Fee: Louise A. Olson

Other Fee: _____

Total Fee: _____

Receipt # 148596

50603



Construction Site Erosion Control Permit Application Fee Schedule for Small Sites

Activity/Project	Non-Waterfront	Waterfront
Deck/Gazebo (Post-Hole Construction)	\$50.00	\$75.00
Deck/Gazebo (Excavation planned)		
Less than 10,000 square feet disturbed	\$100.00	\$200.00
More that 10,000 square feet disturbed	\$150.00 + 0.005 sq. ft. area disturbed	\$300+ 0.005 sq. ft disturbed
Stairway (Post Hole Construction)	\$50.00	\$75.00
Stairway/walkway (Excavation planned)		
Less than 10,000 square feet disturbed	\$100.00	\$200.00
More that 10,000 square feet disturbed	\$150.00 + 0.005 sq. ft. area disturbed	\$300.00+ 0.005 sq. ft. disturbed
Pool (above-ground)	\$100.00	\$200.00
Pool (in-ground) Less than 10,000 sq. ft. disturbed	\$150.00	\$200.00+0.005 sq. ft. disturbed
More that 10,000 sq. ft. disturbed	\$150.00 + 0.005 sq. ft. disturbed	\$300.00+ 0.005 sq. ft. disturbed
Pond/ Pond Maintenance		
Less than 10,000 square feet disturbed	\$150.00 + 0.005 sq.ft. .disturbed	\$200.00+0.005 sq. ft. disturbed
More that 10,000 square feet disturbed	\$150.00 + 0.005 sq. ft. disturbed	\$300.00+ 0.005 sq. ft. disturbed
Demolition		
Less than 10,000 square feet disturbed	\$100.00	\$200.00
More that 10,000 square feet disturbed	\$150.00 + 0.005 sq. ft. disturbed	\$300.00+0.005 sq. ft disturbed
Driveway/Roadway		
Less than 2,500 square feet disturbed	\$ 50.00	\$200.00
More than 2,500 square feet disturbed	\$150.00 + 0.005 sq. ft. disturbed	\$300.00+0.005 sq. ft. disturbed
Boathouse Construction	N/A	\$200.00
Utility Construction, no structures		
Less than 300 linear feet of installation	\$150.00	\$300.00+0.075 linear feet
More than 300 linear feet of installation	\$150.00 + 0.075 linear feet	\$300.00+0.075 linear feet
Utility Construction, with structures	\$150.00 + 0.075 linear feet	\$300.00+0.075linear feet
Landscaping,		
Less than 10,000 square feet disturbed	\$150.00	\$200.00
More that 10,000 square feet disturbed	\$150.00 + 0.005 sq. ft. disturbed	\$300.00 +0.005 sq. ft disturbed
Spoil Spreading and		
Other Land Disturbing Activities		
Less than 10,000 square feet disturbed	\$150.00	\$200.00
More that 10,000 square feet disturbed	\$150 + 0.005 square feet	\$300.00 +0.005 square feet
Compliance Inspection Fee	\$100.00 for each inspection	\$100.00 for each inspection
Ordinance Citation Forfeiture	\$663.00 for each offense	\$663.00 for each offense
Starting work without permit	Double Permit Application Fee Assessed	

LAND USE AND-RESOURCE
MANAGEMENT DEPARTMENT

100 WEST WALWORTH STREET
ROOM 222
ELKHORN, WI 53121
262-741-4972 TEL
262-741-4974 FAX
GN 000148596

Date 11/15/2010

Received of: KOCHANIAK, WANDA & ZBIGNIEW
For: KOCHANIAK, WANDA

Amount: \$300.00

How Paid: CK 500.00

CK #2021 / TAX KEY #CCR 00069 / RCHMND

Init: WB

Return: 200.00

Account Number Description
1360 -43705 - EROSION CONTROL

Amount Code Qty Tax
300.00 CERS 1

Walworth County
Residential Building Construction Erosion Control Permit

Wanda Kochaniak
Permit Applicant

148596
Permit #

Conditions of Permit Approval

1. Tracking of material and soil from the project site onto adjacent roadways will be prevented. A stabilized pad of stone aggregate, consisting of 3" to 6" clear or washed stone, placed 12" thick, the full width of the egress point and 50' long will be installed and maintained, at the location shown on the site plan submitted, will be used for all vehicles and equipment entering and leaving the construction site, (Comm. 21.125 (C)).
2. Any sediment tracked onto a public or private roadway from the project site must be removed by the end of the workday. Off-site sediment deposition occurring as a result of a storm event shall be cleaned up no later than one day following the event, (Comm. 21.125 (1)(d)).
3. The area of land disturbance shall be limited to that area that has been shown on the site plan submitted.
4. All land disturbed, including stockpiled soil and material will be contained. A Silt Fence will be placed where surface water flows off the site, (Comm. 21.125 (1)(a)) at the location:

☐ Shown on the site plan submitted

☒ Shown on site plan revised by Land Conservation Department

Silt fences must be installed and maintained according to the standards and specifications contained in WDNR Conservation Practice Standard 1056 for Silt Fence. The Silt fencing will be inspected after each rainfall event and at least each week and cleaned, repaired, reset or replaced, if necessary. Silt fencing will be dismantled and removed after the project site is stabilized with vegetation.

5. Stockpiled soil must be contained and must not be placed within 25' of any public / private roadway or drainage-way. Avoid placing any stockpiled soil or material on the property line. Any Soil transported off the project site may require additional approvals.
6. All building waste material will be properly managed and disposed of to prevent pollutants and debris from being carried off site. (Comm. 21.125 (f)).
7. Site de-watering is not approved for this project site.
8. Land disturbance, filling, excavating, grading, tree or shrub removal is NOT approved within 75 feet of any lake, creek, or other waterbody, (or the approved shoreyard set-back distance) if present on or adjacent to the project site.
9. This permit is not valid until the applicant has obtained all required federal, state, county and town permits, if necessary.
10. Other _____

Project Site Restoration, Seeding, Mulching and Landscaping.

11. All disturbed areas will be seeded and mulched by: 6-1-11. Any failed seeding will be re-planted and mulched by: 9-15-11.

Seeding and mulching application rates and procedures will be conducted according to the WDNR conservation practice standards or the USDA, NRCS Technical Guide, Section IV.

Walworth County Land Conservation Division
Recommended For Approval:

Louise A. Olson

Date:

11-30-10

[illegible]