

NOTE: DEPTH OF STONE TO BE FIELD DETERMINED AT TIME OF EXCAVATION

SILT FENCE SHALL BE INSTALLED CONTINUOUS AROUND ALL INFILTRATION TRENCHES AND MANHOLES AND SHALL REMAIN UNTIL A PERMANENT VEGETATION COVER HAS BEEN ESTABLISHED (TYP.)

GRASSED AREA

#2 STONE OVER FABRIC WRAP

STONE = 985.5'

BEEHIVE FRAME & GRATE

BEEHIVE R-2540-R

RIM ELEV. = 985.5'

16'x5' TRENCH

42" I.D. DIAMETER PRECAST MANHOLE W/ OPEN BOTTOM

981.5'

12" - #2 STONE BASE

977.5'


GEOTEXTILE FABRIC, TYPE DF OVER TOP AND ON SIDE

STONE INFILTRATION TRENCH MANHOLE

N.T.S.

PROJECT NO.	7455
DATE	10/09/2007
SHEET NO.	1 OF 1



  
PETER S. GORDON R.L.S. 2101

009-1063