


PLAT OF SURVEY

The east part of Block 14 and 17 and the land that lies directly south of the said Block 17 and west of the gravel road, known as Washington Street on the Original Plat of Allen's Grove, all being in the N.E. 1/4 of section 6, T.17. N. 15 E. of the 4th P.M., and being in the Village of Allen's Grove, Town of Sharon, Walworth County, Wisconsin, described as follows:

Beginning on the center line of the concrete highway running from Milwaukee to Beloit, now known as State Highway No. 15, at the Northeast corner of said Block 14 and four hundred seventy-three and one tenth (473.1) feet  $S.75^{\circ}20'W.$  from the intersection of said center line with the center line of the gravel road known as Washington Street on the said Original Plat; running thence  $S.75^{\circ}20'W.$  along the center line of said Highway No. 15, highway known as Milwaukee Street on the said Original Plat, four hundred twenty five and five tenths (425.5) feet to a point; thence  $S.2^{\circ}40'E.$  along the present property line fence, three hundred eighty-nine and two tenths (389.2) feet to an iron pipe monument; thence  $S.78^{\circ}06'E.$  along the present property line fence four hundred thirty and five tenths (430.5) feet to an iron pipe monument; thence  $S.3^{\circ}48'E.$  along the present property line fence seven hundred fifty-five and six tenths (755.6) feet to a point of intersection with the center line of the gravel road on said Washington Street; thence  $N.34^{\circ}05'E.$  along the center of the said gravel road seven hundred fifty-eight (758) feet to an iron pipe monument at an angle in said road; thence  $N.3^{\circ}02'E.$  along the center of said gravel road three hundred forty-four (344) feet to an iron pipe monument; thence  $S.87^{\circ}15'W.$  along the present property line fence four hundred sixty-two (462) feet to an iron pipe monument; thence  $S.3^{\circ}30'E.$  along the present property line fence three hundred ninety and six tenths (390.6) feet to the place of beginning, containing 11.70 acres of land.

I, S. J. Sunny, do hereby certify that I have surveyed the above described land according to official records and according to the present lines of actual occupation and possession, and that the plat herein shown is a correct representation of said survey.

Surveyed this 9th day of May, 1938.

  
 S. J. SUNNY  
 TOWN CLERK SURVEYOR  
 Janesville, Wisconsin.

