

# Property Exhibit

of


## Part of Lot 4 of Certified Survey Map No. 3342,

recorded in Vol. 19 of Certified Survey Maps of Walworth County on Page 76 and located in the Southwest 1/4 of Section 34, Town 2 North, Range 17 East, Town of Geneva, Walworth County, Wisconsin. See Warranty Deed recorded as Document No. 629318.


Prepared for: **Woods School**  
N2575 Snake Road  
Lake Geneva, Wisconsin. 53147

Lot 1  
C.S.M. 3342

Lot 2  
C.S.M. 3342



Bearings reference to Certified Survey Map No. 3342..



**Ecko Lane**  
(86' Wide Private Road)

**Proposed Private Road**  
**Proposed 20' Wide Easement**

**Proposed Shed**

Location of buried water line as indicated by painted marking by others.

**Proposed Lot Line Adjustment**  
**Tax Parcel JA334200004**  
to  
**Tax Parcel JA334200003**

0.069 Acre  
3,018 Sq.Ft.

**Tax Parcel**  
**JA 334200003**

**Tax Parcel**  
**JA334200004**


Approx. 3.090 Acres  
Approx. 134,617 Sq.Ft.  
Approx. 2.091 Acres  
Approx. 91,100 Sq.Ft.  
Exclusive of Private Road

This lot line adjustment is for the purpose of a sale or exchange of land between adjoining land owners that does not create additional lots and the original parcels are not reduced below the minimum size required by the Walworth County Code of Ordinances (Zoning/Shoreland Zoning).

### Legal Description of Proposed Lot Line Adjustment

Part of Lot 4 of Certified Survey Map No. 3342, recorded in Vol. 19 of Certified Survey Maps of Walworth County on Page 76 and located in the Southwest 1/4 of Section 34, Town 2 North, Range 17 East, Town of Geneva, Walworth County, Wisconsin, described as follows: Commencing at the Southwest Corner of said Section 34; thence North 0°10'00" East, along the West line of said Southwest 1/4 of Section 34, 658.61 feet; thence South 89°41'28" East, along the South line of Certified Survey Map No. 3342, 475.38 feet; thence North 0°18'32" East 217.00 feet to an iron pipe and the Point of Beginning; thence North 0°11'16" East 52.00 feet; thence North 69°55'48" East 62.51 feet to an iron pipe at a Northwest corner of Lot 3 of said Certified Survey Map No. 3342; thence Southwesterly along the arc of a curve to the right (Radius=60.05 feet, Chord bears South 38°43'12" West 94.14 feet) 108.19 feet to the Point of Beginning.

Said parcel contains 0.069 acre (3,018 sq.ft.) of land, more or less.




#### Notes:

- This Property Exhibit is not an original unless signed and sealed in red ink.
- This exhibit is subject to Wisconsin lien laws. This Property Exhibit is the notice of intent to file lien. Lien waiver required.

Copyright 2013 by Jensen & Olson Land Surveying, LLC.

All rights reserved. No part of this survey plat may be reproduced or transmitted in any form by any means - graphic, electronic, or mechanical, including photocopying, tracing, or information storage and retrieval systems - without permission in writing from Douglas G. Olson, Jensen & Olson Land Surveying, LLC.



I, Douglas G. Olson, Wisconsin Registered Land Surveyor, do hereby certify that this survey was performed by me, or under my direction in full compliance with the owner's/agent's instructions and Chapter A-E 7 of the Wisconsin Administrative Code "Minimum Standards for Property Surveys"; and that this map is an accurate representation thereof to the best of my knowledge and belief.

Douglas G. Olson  
Wisconsin Registered Land Surveyor - 2093

West line of the Southwest 1/4 of Section 34-2-17.

(N0°10'00"E 658.61')

Southwest Corner  
Section 34-2-17

**Snake Road**  
(66' Wide)

(N1°18'46"E 303.05')

(N1°18'46"E 217.04')

(N89°41'28"W 422.01')

**Tax Parcel**  
**JG 3400021**

(S0°18'32"W 217.00')

(S89°41'28"E 136.65')

(N0°18'32"E 140.00')

#### Legend

- Found Iron Pipe
- Recorded Information
- Gas Sign
- Utility Box or Pedestal
- PVC Pipe
- Asphalt Surface

Sheet 1 of 1 Sheets

Drawing Name: Chl 17-2013-062-2013062Exhibit-4

Job Reference Number

**2013.062**

**Jensen & Olson Land Surveying, LLC**  
45 South Wisconsin Street \* P.O. Box 322 \* Elkhorn, Wisconsin. 53121  
Telephone: (262) 723-3434 \* Facsimile: (262) 723-8044  
Email: jensen.olson@elknet.net

Scale in Feet  
1" = 30'

Survey Date: June 19, 2013.  
Revisions: No. 1A - Proposed Easement  
No. 2A - Proposed Road, Lot  
No. 3 - Proposed Road, Lot  
No. 4 - Line Adjustment &  
No. 5A - Shed  
No. 6A - Legal Description

**2013.062**

JA3342-4  
JA3342-3

217-3900